

US-89, Kanab to Kanab Creek Project

Project Overview

This project has identified transportation solutions for needed safety and maintenance improvements to US-89 from the 300 North Street intersection in Kanab, Utah (R.P. 65.5) north 3.2 miles to the Kanab Creek Bridge (R.P. 68.7). Along this stretch of US-89 there are deficient horizontal curves (at R.P. 66.5), narrow shoulders, roadside hazards, and pavement cracking. To address these deficiencies, the final project will include roadway reconstruction in specific areas to improve horizontal curvature, pavement resurfacing, and shoulder widening.

This project will make the following roadway improvements to US-89 between the 300 North intersection in Kanab and the Kanab Creek Bridge:

- Widen shoulders to 6-feet
- Rehabilitate the asphalt pavement
- Improve sight distance near the Kanab Creek Pond
- Add a southbound left-turn lane at the 300 North Intersection
- Improve storm drainage by reducing ponding/flooding on and near the roadway
- Improve acceleration and deceleration lanes at the port-of-entry station



Project Schedule

The environmental documentation and preliminary design are complete. The following timeline outlines when the remaining project activities will take place (schedule is subject to change):

Final Design Complete	December 2007
Advertise for Construction	December 2007
Construction Set to Begin	February 2008

Contact Information

For more information regarding the project or to provide comments, please

contact Randi Shover at:

Email: kanabcreek@hwlochner.com

Phone: (801) 262-8700

Information is also available on the project web site at www.udot.utah.gov/kanabcreek.

Stay up-to-date on project activities

Want to receive the latest information regarding the Kanab to Kanab Creek Project? Sign-up for email updates by simply sending your email address to the project team at the following address:

kanabcreek@hwlochner.com

Thank you and we look forward to working with you!