

**Supplemental Specification
2005 Standard Specification Book**

SECTION 01721M

SURVEY

Delete Article 1.1, Paragraph A, and replace with the following:

- A. Schedule, coordinate, and provide all construction surveying, staking, measurement, and calculations essential to complete the project and properly control the entire work.

Delete Article 1.2 and replace with the following:

- A. Section 01280: Measurement
- B. Section 02765: Pavement Marking Paint

Delete Article 1.5, Paragraphs F and G and replace with the following:

- F. After project completion, return to the Engineer all surveying and design data and provide a red-lined hard copy plan set showing as-constructed features denoting changes from the original design.

Delete Article 3.3, Paragraph C.

Delete Article 3.11, and replace with the following:

3.11 GUARDRAIL AND CRASH CUSHION

- A. Stake guardrail vertical and horizontal control at a maximum spacing of 25 ft on tangent sections and 10 ft on curved sections unless otherwise approved.
- B. Obtain Engineer's approval and field verification of staking prior to installation.