



Agenda

Project History and Funding

Procurement

Innovation to Meet Project Goals

Progress Update



Project Need


- EIS initiated in 2004
- Utah County annual growth rate of 5.5%
- Projected 2030 Utah County population: 907,210 (a 22-year growth rate of 75%)
- Aging infrastructure 40+ years old





Project Background


- EIS from 12300 South to South Payson
- 43-mile corridor estimated cost: \$5 billion
- 2008 Legislature planned: \$2.63 billion
- 2009 Legislature allocated: \$1.725 billion
- Motto 1: Be Flexible





I-15 CORE Plan

- \$1.725 billion allocated
- Project funded from American Fork Main Street to Provo Center Street
- Motto 2: Stretch South





Why Design-Build?

- Shorter overall schedule
- Single entity controlling design and construction
- Better risk allocation
- Flexible scope
- Fixed price




Fixed-Price, Best-Design Approach

- Bidders develop highest-value, creative solution for fixed construction budget
- Proposals evaluated on meeting or exceeding defined criteria, based on project goals
- Fosters competition, innovation
- Best opportunity to achieve the most length, greatest number of improvements for set price



Fixed-Price Procurement Process





Project Goals

Project goals and values approved by Transportation Commission:

Deliver I-15 CORE within the Budget

Provide the Highest Value for the Budget

Minimize Inconvenience to the Public

Complete I-15 CORE by 2014

Uphold the Public Trust



Procurement Schedule

Released RFQ: April 2009

Design-builders submitted SOQs: May 2009

Short listed design-builders: May 2009

Commission endorsed values statement: May 2009

Issued RFP: June 2009

Conducted industry outreach and technical proposal discussions:

June – October 2009

Design-builders submitted proposals: November 19, 2009


Announced selected design-builder: December 9, 2009

Issued NTP1: January 14, 2010

Issued NTP2: April 19, 2010



Proposal Evaluation





Selected Design-Build Team


Provo River Constructors:

- Fluor Enterprises
- Ames Construction Company
- Ralph L. Wadsworth Construction Company
- Wadsworth Brothers Construction Company
- Fluor/HDR Global Design Consultants
- Michael Baker Jr.
- Jacobs Engineering Group
- H.W. Lochner
- Kleinfelder West

- Intermountain GeoEnvironmental Services
- CRS Consulting Engineers
- Raba-Kistner Consultants
- TransCore IP
- Stillwell & Associates
- Applied Research Associates
- Fehr & Peers Transportation Consultants
- Psomas
- CME Transportation Group



Final Project Scope





PRC Proposal

- Provided best balance of scope, schedule and MOT
- 40-year concrete pavement along entire corridor
- Current number of lanes open both southbound and northbound during the majority of construction
- Accelerated schedule



Minimize Inconvenience to the Public

UDOT Goal:

Minimize Inconvenience to the Public

Contractor Solutions:

- 1. Maintenance of Traffic Plan
- 2. Accelerated Bridge Construction



LANES

CONSTRUCTION AREA

TRAVEL LANES

INTERCHANGES


INTERCHANGE

INTERCHANGE

RECONSTRUCTED


MODIFIED/IMPROVED

Phase 1 Traffic Configuration





Phase 2 Traffic Configuration






Head-to-Head Traffic Configuration





Inside-Outside Traffic Configuration





Keeping Orem Center Street Interchange Open


 Traffic moved to inside while outside is reconstructed





Keeping American Fork 500 East Open


 Old bridge was operational while new bridges were constructed on both sides





Accelerated Bridge Construction

- 6 bridge moves on I-15 CORE
- Other ABC techniques in use throughout







Construction Progress






Progress Update

- Notice to Proceed 2 April 19, 2010
- Expending about \$1 million a day
- 97% design completion to date
- Project currently 1/3 complete
- Current PRC staff and crew: 1,400



Earth Work


• 3.7 million tons of fill





Bridges


• 31 bridges currently under construction





Drainage

• 22 miles of pipeline laid





Concrete Paving

- 405,000 square yards of concrete placed to date
- 57 lane miles completed





Project Schedule

2011

- Phase 2 traffic shift onto permanent roadway
- Three bridge moves
- Extensive interchange work in all areas
- Continued paving and bridge work

2012

- Lehi and American Fork completion in June
- Project completion in December



For More Information

Weekly e-mail updates: sign up at udot.utah.gov/i15core

Website: udot.utah.gov/i15core

Text messaging: text "i15" to 53535

E-mail: i15core@utah.gov

Hotline: 1-888-i15core

(1-888-415-2673)

Facebook: facebook.com/i15core

Twitter: twitter.com/i15core

