

**Supplemental Specification
2017 Standard Specification Book**

SECTION 13553M

ATMS CONDUIT

Delete Article 3.2, Paragraph H2 and replace with the following:

2. Use 6 inches of sand backfill covered with native material in all other areas.

Delete Article 3.3, Paragraph C3b and replace with the following:

- b. Provide 6 inches of sand backfill above conduit in trench.
 - 1) Backfill trench above sand to finished grade using native material.
 - a) Backfill and tamp in 6 inch lifts.