

## ABC Project Highlights

Project Name: I-15 Bridge Deck Replacements; Payson

Project #/PIN #: F-R399(30) / 6418

Year Constructed: 2009

ABC Element(s): Full Depth Deck Panels

Placement Method:

Contracting Method: Design-Build

Project Description: This design-build project replaced six deteriorating bridge decks, structural concrete rehabilitation work and a ramp widening with intersection improvements. The bridges are located in Payson, Utah at Main Street, 400 north, and Utah Avenue. The work consisted of removing the existing decks with care to prevent damage to the existing girders and replacing them with full depth precast deck panels and a polymer overlay. The concrete deck panels were longitudinally post-tensioned.





