

**Supplemental Specification
2017 Standard Specification Book**

SECTION 02221M

REMOVE STRUCTURE AND OBSTRUCTION

Delete Article 3.21 and replace with the following:

3.21 REMOVE CATTLE GUARD

- A. Salvage existing traffic grill units and welded end guard units.
 - 1. Contact the Engineer for delivery location and coordination for salvaged traffic grill units and welded end guard units.
- B. Cut existing pavement as required. Refer to Section 02705.
- C. Remove existing fence as required.
- D. Remove the cattle guard to at least 2 ft below the subgrade surface or finished ground lines.
- E. Prevent livestock from entering work site from adjacent properties during removal and installation.