

State Route 73

RENEWED

MP 15.79 to 25

UDOT to Resurface Nine-mile Segment Between Cedar Fort and Utah/Tooele County Line

Beginning June 7, 2017, and continuing through mid-August 2017, the Utah Department of Transportation (UDOT) will resurface 9 miles of State Route 73 from the Tooele County line to Cedar Fort.

Construction crews will use a process called hot-in-place recycling (HIR). The HIR process allows workers to reuse the existing asphalt surface by grinding off a specific depth of the pavement, mixing the asphalt with a recycling agent, and repaving the road with the reprocessed asphalt. Once the recycled layer is placed, a layer of new asphalt is placed on the recycled portion and then crews will place a final chip seal on the new asphalt roadway.

Anticipated Travel Delays

To complete the work, crews will close one lane of traffic between **7 a.m. and 8:30 p.m. Monday through Thursday**, and **Friday from 7 a.m. to 3 p.m.** Flaggers will be posted at each end of the work zone to direct drivers safely through the project area. The speed limit will be lowered and the travel lane will be reduced to 11 feet wide. Motorists should anticipate travel delays. Please slow down when driving through construction zones and watch out for crews working within the area.

For more information about this project, please contact the project representative at **877-495-4240**, or via email at udotregion3@utah.gov. Work schedules are subject to change due to inclement weather, equipment problems, or emergency situations.

